



01 PROJECT PREPARATION

pro_PART_CODE	Supp SKU	Description	Supp Description	UsedCost	Supp Unit	Supp Zip Code
RM11772035		Sand & fill foundation walls in Tons where 1.5 Yards is 1 Ton	Sand & fill foundation walls in Tons where 1.5 Yards is 1 Ton	\$10.00	138	

Sub Total Material \$0.00

07 CONCRETE

pro_PART_CODE	Supp SKU	Description	Supp Description	UsedCost	Supp Unit	Supp Zip Code
RM10326007	8013000	Place #3 (3/8 in) steel rods-rebar 24 in o.c. to reinforce concrete wall	Place #3 (3/8 in) steel rods-rebar 24 in o.c. to reinforce concrete wall	\$11.87	EA	23435
RM10326407		Embed 4 in deep into Concrete footing and install 12 Gauge- 2 in wide strap anchor per pier.	Embed 4 in deep into Concrete footing and install 12 Gauge- 2 in wide strap anchor per pier.	\$1.00	EA	
RM10245807		Pour continuous footing 10 inD x 20 inW wheeled reinforced. No forms or excavation included.	Pour continuous footing 10 inD x 20 inW wheeled reinforced. No forms or excavation included.	\$115.00	CY	

Sub Total Material \$2,006.67

08 MASONRY

pro_PART_CODE	Supp SKU	Description	Supp Description	UsedCost	Supp Unit	Supp Zip Code
RM10342008		Construct block wall 8 in W x 8 in H x 16 in L concrete lightweight unreinforced. No footing included.	Construct block wall 8 in W x 8 in H x 16 in L concrete lightweight unreinforced. No footing included.	\$1.00	EA	
RM10373208		Apply waterproof paint 2 coats	Apply waterproof paint 2 coats	\$54.00	EA	
RM11030220		Install 8 in x 14 in foundation vent galvanized	Install 8 in x 14 in foundation vent galvanized	\$15.00	EA	
Sub Total Material				\$1,153.00		

09 FLOOR FRAMING

pro_PART_CODE	Supp SKU	Description	Supp Description	UsedCost	Supp Unit	Supp Zip Code
RM10400719		Install on Sill Plate Foundation Wall with Anchor Bolts	Install on Sill Plate Foundation Wall with Anchor Bolts	\$1.00	EA	
RM10940018		Install joists 2x8x16 Floor Joist	Install joists 2x8x16 Floor Joist	\$14.00	EA	
RM10940018		Install joists 2x8x16 Floor Joist	Install joists 2x8x16 Floor Joist	\$14.00	EA	
RM10409410		Install plywood sheathing Plytanium 23/32 x 4 x 8 Sturd-I-Floor T&G Plywood	Install plywood sheathing Plytanium 23/32 x 4 x 8 Sturd-I-Floor T&G Plywood	\$19.00	EA	
Sub Total Material				\$4,115.00		

10 WALL FRAMING

pro_PART_CODE	Supp SKU	Description	Supp Description	UsedCost	Supp Unit	Supp Zip Code
RM10494612		Apply self-adhering underlayment tape to joints of Drywall Sheathing.	Apply self-adhering underlayment tape to joints of Drywall Sheathing.	\$7.00	ROLL	
RM10417410	2041601	Install studs 2 in x 4 in 16 in o.c. 16 ft tall	Install studs 2 in x 4 in 16 in o.c. 16 ft tall	\$6.73	EA	23435
RM10417410	2041601	Install studs 2 in x 4 in 16 in o.c. 16 ft tall	Install studs 2 in x 4 in 16 in o.c. 16 ft tall	\$6.73	EA	23435
RM10417410	2041601	Install studs 2 in x 4 in 16 in o.c. 16 ft tall	Install studs 2 in x 4 in 16 in o.c. 16 ft tall	\$6.73	EA	23435
RM10437411		Install plywood sheathing 7/16 in	Install plywood sheathing 7/16 in	\$9.00	EA	
RM10417410	2041601	Install studs 2 in x 4 in 16 in o.c. 16 ft tall	Install studs 2 in x 4 in 16 in o.c. 16 ft tall	\$6.73	EA	23435
RM10417410	2041601	Install studs 2 in x 4 in 16 in o.c. 16 ft tall	Install studs 2 in x 4 in 16 in o.c. 16 ft tall	\$6.73	EA	23435
RM10403810		Install 2 in x 6 in 16 in o.c. wood frame wall up to 8 ft tall	Install 2 in x 6 in 16 in o.c. wood frame wall up to 8 ft tall	\$1.00	EA	
RM10403010	2041201	Existing 2 in x 4 in 16 in o.c. wood frame wall up to 12 ft tall	Existing 2 in x 4 in 16 in o.c. wood frame wall up to 12 ft tall	\$5.04	EA	23435

RM10402610		Install 2 in x 4 in 10 ft 16 in o.c. wood frame wall up to 10 ft tall	Install 2 in x 4 in 10 ft 16 in o.c. wood frame wall up to 10 ft tall	\$2.00	EA	
------------	--	---	---	--------	----	--

RM10402610		Install 2 in x 4 in 10 ft 16 in o.c. wood frame wall up to 10 ft tall	Install 2 in x 4 in 10 ft 16 in o.c. wood frame wall up to 10 ft tall	\$2.00	EA	
------------	--	---	---	--------	----	--

RM10402610		Install 2 in x 4 in 10 ft 16 in o.c. wood frame wall up to 10 ft tall	Install 2 in x 4 in 10 ft 16 in o.c. wood frame wall up to 10 ft tall	\$2.00	EA	
------------	--	---	---	--------	----	--

RM10402410	2049201	Install 2 in x 4 in 16 in o.c. wood frame wall up to 92-5/8 ft tall	Install 2 in x 4 in 16 in o.c. wood frame wall up to 92-5/8 ft tall	\$3.14	EA	23435
------------	---------	---	---	--------	----	-------

RM10401810		Install 2 in x 4 in 16 in o.c. wood frame wall up to 14 ft tall	Install 2 in x 4 in 16 in o.c. wood frame wall up to 14 ft tall	\$3.00	EA	
------------	--	---	---	--------	----	--

RM10417410	2041601	Install studs 2 in x 4 in 16 in o.c. 16 ft tall	Install studs 2 in x 4 in 16 in o.c. 16 ft tall	\$6.73	EA	23435
------------	---------	---	---	--------	----	-------

Sub Total Material \$4,703.09

11 ROOF FRAMING

pro_PART_CODE	Supp SKU	Description	Supp Description	UsedCost	Supp Unit	Supp Zip Code
---------------	----------	-------------	------------------	----------	-----------	---------------

RM10443031		Install clips/straps to connect rafters or trusses to wall in new roof framing	Install clips/straps to connect rafters or trusses to wall in new roof framing	\$4.00	EA	
------------	--	--	--	--------	----	--

Sub Total Material \$684.00

12 ROOFING AND GUTTERS

pro_PART_CODE	Supp SKU	Description	Supp Description	UsedCost	Supp Unit	Supp Zip Code
RM10499517		Remove & replace fiberglass shingles over 8/12 slope. EA = up to 5 individual shingles SQ	Remove & replace fiberglass shingles over 8/12 slope. EA = up to 5 individual shingles SQ	\$31.00	BNDL	
RM10454812	3056400	Install Owens Corning 25-Year Supreme Desert Tan AR 3 Tab Shingles	Install Owens Corning 25-Year Supreme Desert Tan AR 3 Tab Shingles	\$3.29	BNDL	23435
RM10494412	23000	Supply & Install #30 Felt Paper over Roof Decking	Supply & Install #30 Felt Paper over Roof Decking	\$21.99	ROLL	23435
RM10494812	4929800	Install aluminum drip edge	Install aluminum drip edge	\$2.59	EA	23435
RM10496612		Install aluminum stepflashing in open joints	Install aluminum stepflashing in open joints	\$2.00	ROLL	
RM10499412	6992600	Install continuous ridge vent shingle over style installation only	Install continuous ridge vent shingle over style installation only	\$13.19	ROLL	23435
RM10499012		Install continuous ridge vent, shingle over style, cut roofing & install	Install continuous ridge vent, shingle over style, cut roofing & install	\$2.00	ROLL	
RM10513212		Install 5 in seamless aluminum guttering	Install 5 in seamless aluminum guttering	\$1.00	EA	

RM10516812		Install 2 in x 3 in vinyl downspout	Install 2 in x 3 in vinyl downspout	\$1.00	EA	
------------	--	-------------------------------------	-------------------------------------	--------	----	--

RM10498812		Install continuous ridge vent aluminum cut roofing & install	Install continuous ridge vent aluminum cut roofing & install	\$3.00	BNDL	
------------	--	--	--	--------	------	--

Sub Total Material

\$2,997.94

13 EXTERIOR DOORS

pro_PART_CODE	Supp SKU	Description	Supp Description	UsedCost	Supp Unit	Supp Zip Code
---------------	----------	-------------	------------------	----------	-----------	---------------

RM10530813		Install Kwikset SmartKey Antique Brass Residential Single-lock Door Handleset	Install Kwikset SmartKey Antique Brass Residential Single-lock Door Handleset	\$119.00	EA	
------------	--	---	---	----------	----	--

RM10557213		Install pre-hung 3-0 x 6-8 fir/pine french exterior door unit with 5 lites. Removal of old exterior door not included.	Install pre-hung 3-0 x 6-8 fir/pine french exterior door unit with 5 lites. Removal of old exterior door not included.	\$229.00	EA	
------------	--	--	--	----------	----	--

Sub Total Material

\$348.00

15 VINYL WINDOWS

pro_PART_CODE	Supp SKU	Description	Supp Description	UsedCost	Supp Unit	Supp Zip Code
RM10802815		Install 3-0 x 3-6 double hung window insulated glass vinyl. Removal of old window not included.	Install 3-0 x 3-6 double hung window insulated glass vinyl. Removal of old window not included.	\$266.00	EA	

Sub Total Material

\$5,320.00

18 DECKS AND PORCHES

pro_PART_CODE	Supp SKU	Description	Supp Description	UsedCost	Supp Unit	Supp Zip Code
RM10938218		Install joists 2x8x12 pressure treated Sill	Install joists 2x8x12 pressure treated Sill	\$10.00	EA	
RM10940818		Install joists 2 in x 4 in x 16 Firn all sides 16 in o.c.	Install joists 2 in x 4 in x 16 Firn all sides 16 in o.c.	\$2.00	EA	
RM10950318		Install surface composite drywall screws economy grade	Install surface composite drywall screws economy grade	\$19.00	LBS	

Sub Total Material

\$459.00

19 SIDING AND AWNINGS

pro_PART_CODE	Supp SKU	Description	Supp Description	UsedCost	Supp Unit	Supp Zip Code
RM10991649		Remove & replace vinyl siding. EA 12 Sticks at 12 LF per stick and 288 sq ft or 2 sq of siding per box.	Remove & replace vinyl siding. EA 12 Sticks at 12 LF per stick and 288 sq ft or 2 sq of siding per box.	\$1.00	SQUARES	
RM10994019	7441000	DuPont Tyvek 9-ft x 150-ft House Wrap	DuPont Tyvek 9-ft x 150-ft House Wrap	\$184.79	ROLL	23435

Sub Total Material

\$320.15

20 EXTERIOR TRIM

pro_PART_CODE	Supp SKU	Description	Supp Description	UsedCost	Supp Unit	Supp Zip Code
RM11000220	1061601	Install fir/pine fascia 1 in x 6 in	Install fir/pine fascia 1 in x 6 in	\$9.44	EA	23435

Sub Total Material

\$141.60

27 INSULATION

pro_PART_CODE	Supp SKU	Description	Supp Description	UsedCost	Supp Unit	Supp Zip Code
RM11272427		Install insulation R-19 unfaced rafters 6-1/4 in thick x 15 in wide 16 in o.c. SB	Install insulation R-19 unfaced rafters 6-1/4 in thick x 15 in wide 16 in o.c. SB	\$38.00	ROLL	
RM11274827		Install insulation R-30 unfaced laid flat 9-1/2 in thick x 16 in wide 16 in o.c.	Install insulation R-30 unfaced laid flat 9-1/2 in thick x 16 in wide 16 in o.c.	\$11.00	EA	

Sub Total Material

\$826.55

28 WALL COVERINGS

pro_PART_CODE	Supp SKU	Description	Supp Description	UsedCost	Supp Unit	Supp Zip Code
RM11300028		Install 1/2 in drywall hung only.	Install 1/2 in drywall hung only.	\$13.00	EA	

Sub Total Material

\$1,014.00

30 INTERIOR DOORS

pro_PART_CODE	Supp SKU	Description	Supp Description	UsedCost	Supp Unit	Supp Zip Code
RM11375630		Install interior lock set premium quality	Install interior lock set premium quality	\$96.00	EA	

Sub Total Material

\$96.00

31 INT TRIM STAIRS AND ACCESSORIES

pro_PART_CODE	Supp SKU	Description	Supp Description	UsedCost	Supp Unit	Supp Zip Code
RM11450231		Install pine casing 5/8 x 2-1/2 decorative	Install pine casing 5/8 x 2-1/2 decorative	\$1.00	LF	
RM11495631		Install Baseboards with a Paint Finish or Natural	Install Baseboards with a Paint Finish or Natural	\$3.00	LF	

Sub Total Material

\$1,197.01

33 FLOOR COVERING

pro_PART_CODE	Supp SKU	Description	Supp Description	UsedCost	Supp Unit	Supp Zip Code
RM11636633		Labor to install flooring by the sq. yard resilient sheet flooring on wood floor. No flooring materials included SB.	Labor to install flooring by the sq. yard resilient sheet flooring on wood floor. No flooring materials included SB.	\$2.00	SF	
RM11652233		Install 3/4 in T&G OSB subfloor	Install 3/4 in T&G OSB subfloor	\$32.00	EA	
RM11687233	2080804	Install joists 2x8x8 16 in o.c.	Install joists 2x8x8 16 in o.c.	\$5.52	EA	23435
RM11687233	2080804	Install joists 2x8x8 16 in o.c.	Install joists 2x8x8 16 in o.c.	\$5.52	EA	23435
RM11687433	2081204	Install joists 2x8x12 16 in o.c. not included.	Install joists 2x8x12 16 in o.c. not included.	\$8.39	EA	23435
RM11687433	2081204	Install joists 2x8x12 16 in o.c. not included.	Install joists 2x8x12 16 in o.c. not included.	\$8.39	EA	23435

Sub Total Material

\$8,903.66

34 EXTERIOR PAINTING

pro_PART_CODE	Supp SKU	Description	Supp Description	UsedCost	Supp Unit	Supp Zip Code
RM11770634		Apply parging 1/2 in thick 2 coats	Apply parging 1/2 in thick 2 coats	\$9.00	CY	

Sub Total Material

\$63.00

35 INT PAINTING AND WALLPAPER

pro_PART_CODE	Supp SKU	Description	Supp Description	UsedCost	Supp Unit	Supp Zip Code
RM11819035		Paint drywall or plaster wall brush 2 coats smooth finish 5-Gal SB	Paint drywall or plaster wall brush 2 coats smooth finish 5-Gal SB	\$126.00	CAN	

Sub Total Material

\$882.00

60

Grand Total Material

\$35,230.67